

31 JUL 1946

Index No.

Lloyd's Register of Shipping.

Ship's Name "LODESTONE".

Official No. 166585.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Restoring of Tonnage Opening.

- (1) The tonnage opening in the Shelter Deck now restored and fitted with temporary wood covers. (Cleats to be removed from B.A. Coaming of Tonnage Hatch on Shelter Deck).
- (2) The tonnage opening on the Tonnage Well forward bulkhead now closed by 3" boards fitted in Channels.
- (3) All scuppers which are led to the Hold Bilges from the Shelter Tween Decks now permanently closed by E.W. plates.
- (4) An overboard scupper 5" in diameter fitted on each side of the Tonnage Well with a screw-down automatic non-return valve controlled from the Shelter Deck with an indicator showing when valve is open or shut.
- (5) All hatchways on the 2nd Deck have coamings, covers, supports, bearing surfaces, tarpaulins, cleats and battening arrangements in accordance with Rules.

B.E. Marborough

SURVEYOR TO LLOYD'S REGISTER.

LIVERPOOL.

30th July, 1946.

Cleats removed from B.A. Coaming of Tonnage Hatch on Shelter Deck at London, on the 9th August, 1946.

C. Lloyd Roberts

SURVEYOR TO LLOYD'S REGISTER

LONDON.

9th August, 1946.

The scupper pipes to the machinery space bilges have been fitted with self closing cocks.

Malcolm

SURVEYOR TO LLOYD'S REGISTER,

SWANSEA.

14th August, 1946.

Noted
B.Y.
15-8-46



© 2020

Lloyd's Register
Foundation