

26 JUN 1941

Index No. 32461

Lloyd's Register of Shipping.


Ship's Name S.S. "Lodestone"

Official No. 166585

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in September 2, 1938

Defense Personnel Quarters have been fitted at the after end of the Shelter Deck Space adjacent to the tonnage well. The tonnage hatch has been permanently closed with a .35" plate electrically welded to top of bulb angle coaming and fitted with two hatches 30" x 30" x 20" high with hinged steel watertight covers and one steel companionway 60" x 30" x 6' high fitted with a steel watertight door, height of sill 20" x Tonnage openings: non-return valves and rods in tonnage well have been removed and the openings in shell and deck closed with welded plates. ✓

Thomas Barrie (Boston)



© 2020

Lloyd's Register
Foundation

003671-083678-0134