

128 DEC 1965

SHIP'S NAME "RIA DE EL FERROL"

PORT ANT

No. 41581

LAST SURVEY DATE 29.10.65.

- CLASS IS SUBJECT TO 1. Evaporator not to be used until surveyed.  
2. Screwshaft be renewed or dealt with by 3.66 (6 months), record of TSCL 9.65 withheld meantime.

SUBJECT ITEM 2. NOW DEALT WITH BY RENEWAL  
TO BE DELETED

DOCKING (W.D. 0.75%)

DAMAGE PROPELLER CONTACT, BLADE TIPS WERE  
FOUND BROKEN & REPAIRED BY CUTTING ALL BLADES  
TO SAME LENGTH (7" SHORTER) & BALANCING STRENGTH.  
THE WORKING & SPARE SCREW SHAFTS WERE REJECTED  
ON ACCOUNT OF CORROSION & A NEW SHAFT HAS BEEN  
FITTED OF LARGER DIA: TO SUIT ENLARGED BORE OF  
PROPELLER REBORED TO REMOVE CORROSION.

It is submitted that this  
beamel is eligible for THE  
RECORD. T.S.O.G N 10.65

SUBJECT AS ABOVE ITEM 1  
WITHOUT ITEM 2

SLAVEYOR SHOULD FORWARD  
SUNDERLAND CERT FOR  
FOR NEW SCREW SHAFT

See ANT. L. 3/1/66

4 30/1/66

003679-003680-0184