

24234

No. 958.
Midship Section.

Scale $\frac{1}{2}$ " = One ft.

Dimensions: 220'-0" B.P. x 36'-0" Mld x 14'-0" Mld to Upper Dk.

To Class 100 A1 Lloyds, Carrying Petroleum or Molasses in Bulk.

Riveting.

Keel. Triple riveted overlaps throughout.
Bottom Shell. Triple riveted laps for 1/2 Lin. to B.R. at ends.
Side Shell. Double riveted for 1/2 Lin. (when not exceeds 1/2) to B.R. at ends.
Streaks below Sheerstrake. Triple riveted for 1/2 Lin. to B.R. at ends.
Sheerstrake. Triple riveted for 1/2 Lin. to B.R. at ends.
Upper Deck Stringer. Double riveted for 1/2 Lin. to B.R. at ends.
Upper Deck Plating. B.R. for 1/2 Lin. to S.R. at ends (Clear of Joists).
Trunk Top Plating. B.R. throughout.
Trunk Bridge. S.R. sides + plating. S.R. end Laps.
Centre Line Bulkhead. Bottom Strake T.L. laps throughout, B.R. elsewhere.
Expansion Trunk Sides. B.R. end Laps throughout.
Deck Longitudinals. Face bars on Transverses. Single Strake on Expansion Trunk sides & Deck.
Transverses to decks. 1/2 Lin. 5 Ribs (except for 1/2 Lin. 5 Ribs).
Side Transverses. 1/2 Lin. 5 Ribs to Shell & Bulkhead 5 Ribs (except for 1/2 Lin. 5 Ribs).

Special attention to be paid to the riveting
workmanship. See section 19 of Lloyd's rules.

DAVID L. LAIRD & CO. LTD.
SHIP DEPARTMENT.

Numerals.

D	=	14
L x D	=	3,080
L x (B+D)	=	11,000
L/D	=	15.7
"d"	=	11.6

Equipment Numeral.

L x (B+D)	=	11,000
Poof 71.5 x 7.5 x 7.5	=	400
Bridge 21.5 x 7.5 x 7.5	=	120
26 Ls 112.0 x 7.5 x 7.5	=	236
Erection on Poof 61.5 x 7.5 x 5.0	=	230
Erection on Bridge 21.5 x 7.5 x 5.0	=	80
Trunk 85.25 x 4.25 x 5.0	=	12,066
	=	181
	=	12,247

Equipment.

2 Power Anchors each 25 1/2 cwt. Stockless	
1 " " 22 cwt. Stockless	
1 Stream Anchor 63 " Ex. Stock.	
210 Fms 1 1/16 Steel chain cable	
75 " 3/4 Steel wire Rops	
90 " 3/4 " " Towing	
1 @ 90 Fms 2 1/2 Steel wire Haulers	
1 @ 90 " 1 1/4 " " Warps	

Midship Transverse.

Midship O.T. Bulkhead.

Bulkhead Web.
10'-0" off P.S.



REGISTERED
21 FEB 1929
LIVERPOOL

LR

Midship Section

S. S. Apollonia

LIVERPOOL

Report No. 96039

"
Activity
"



© 2021

Lloyd's Register
Foundation

5410-912303-0175