

Steam Trawler "FYLDEA".

Present Dimensions:- 140' x 25' x 14'-3".

A letter has been received from the Middlesbrough Surveyors stating that it is proposed to length^{en} this vessel by 8'-2" on the load water line by fitting a new fore end and a cruiser stern. They enclose 5 plans, in triplicate, shewing the proposed modifications.

A similar alteration was carried out at Middlesbrough in the case of the Trawler "LEONIDAS".

The scantlings and arrangements of the "FYLDEA" have been examined and are found to be such as could be accepted for the proposed increased length. The equipment, however, should be increased by supplying an additional length of cable.

It is therefore submitted the Surveyors be informed that provided the scantlings and arrangements be carried out as shewn and amended on the plans and to their satisfaction, the proposal will merit approval.

On account of the alteration to the equipment grade due to the increased length, an additional 15 fathoms of 1.2/16" stud chain cable should be supplied.

Ltr. 17.6.36.
Ansd. 23.6.36.
12 plans.
5 retained.



© 2021 23.6.36
178

Lloyd's Register
Foundation