

an

Bethlehem Fairfield Shipyard Inc.

Yard No. 2258

Chief Ship Surveyor

Received from Chief Ship Surveyor

BE APR 1948

NAME

"IVYBANK"

REPORT

Sws.

No. 24115

Remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

"The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/42.)

This Liberty vessel was built in 1943 and classed with the American Bureau of Shipping.

The vessel holds the notations of 100A1 (Classification Contemplated) and "Examined 8.47".

The notations are subject to permanent repairs to indented shell plating (p & s) at the first convenient opportunity, and to buckled bulkhead between Nos. 1 & 2 holds and 45 fathoms of chain cable being supplied at the first opportunity.


Plans for this type of vessel have been examined in this office and scantlings and arrangements found suitable for the class 100A-

CLASSIFICATION SPECIAL SURVEY was commenced at Liverpool 2.48.

The SWANSEA Surveyors report the vessel afloat and the Classification SPECIAL SURVEY advanced.

A First Entry report completed in accordance with Circular 1871.

TO COMPLETE S.S:- Vessel to be examined in dry dock; anchors and cables to range and verify, and chain locker to be examined internally; rudder to be specially examined, Circular 1870.




On account of contact with lock wall, temporary repairs (electric welded doubler) effected to holed No.6 shell plate in 3rd strake below sheer (s.s) and permanent repairs are recommended at the first convenient opportunity.

45 fathoms of chain cable, as above, and spare bower anchor now placed on board and verified with certificates.

Buckled bulkhead, as above, examined and continues efficient.

Structure reinforcements, etc. as required by 'SAM' ships, found previously effected.



© 2020

Lloyd's Register  
Foundation

003750-003762-0196 1/2



- 2 -

"IVYBANK"

IT IS SUBMITTED this vessel is eligible to have her temporary class continued, subject to permanent repairs to indented plating (p & s) and No. 6 shell plate in 3rd strake below sheer (s.s.) at the first convenient opportunity, <sup>and to buckled bulkhead between Nos. 1 & 2 holds</sup> at the first opportunity, but without other condition.

As now, subject.  
without.

CLASSIFICATION S.S.  
PART HELD.

ST.  
23-3-48



© 2020

Lloyd's Register  
Foundation

0196212

Fourth Deck, amidships, Angle, [ ] or [ ]