

Built at
GENERATOR
Engines made
Monkey Box

GLASGOW REPORT No 46840

GLASGOW,

4th July, 1927.

W. LANE

23-4
29J
8-30
7-30
3-20
10.
27.

Messrs. The Fairfield S. B. & E. Co., Ltd., Govan, attend at their Works on the 13th January, 1926 and subsequent dates, for the purpose of examining and testing four Air Receivers designated Nos. 98, 99, 120, 140, intended to be used in conjunction with the Fairfield Sulzer Oil Engines No. 620 built by the above Firm.

These Air Receivers are stated to have been built to The Admiralty Specifications and the materials tested in accordance with their requirements.

The dimensions of these Receivers have been checked and found to be in accordance with the requirements of this Society for a working pressure of 600 lbs. per square inch. Their condition and workmanship, as far as can be seen, are sound and good.

They were tested in the presence of the undersigned by hydraulic pressure to 1000 lbs. per square inch and showed no signs of weakness, and were tight and sound in every respect at that pressure. Working pressure not to exceed Six Hundred pounds per square inch.

For/



© 2020

Lloyd's Register
Foundation

005769-003777-0022

opping.

For identification the Receivers are marked:-

Two Receivers Nos.98, 99
No.17088
Lloyd's Test.
1000 lbs.
W.P. 600 lbs.
7. 4. 26. W.L.

Two Receivers Nos.120,140.
No.17091
Lloyd's Test.
1000 lbs.
W.P. 600 lbs.
12. 4. 26. W.L.

W. Lane

Surveyor to Lloyd's Register.



© 2020

Lloyd's Register
Foundation

005169-005777-0002 $\frac{2}{2}$