

## EQUIPMENT.

Lx(B+D) 2974.25  
BRIDGE 1220.62  
DECKHOUSE 170.50

Two BOWER ANCHORS  
EACH WEIGHING 33½ CWTs  
PER LONDON LETTER  
To S. H. & W. R.  
30x10x24.

EQUIPMENT No 11,365.37.

1. STREAM ANCHOR 6 CWTs. EX. STOCK.  
210 FATHOMS OF 1" 11/16" STUD CHAIN CABLE  
60 FATHOMS OF 3/8" STEELWIRE STREAM  
90 FATHOMS OF 3/4" STEEL WIRE TOWLINE  
90 FATHOMS OF 2 1/4" STEEL WIRE HAWKERS  
90 FATHOMS OF 1 3/4" STEEL WIRE WARPS.

210'-0" O.A. (LLOYDS LENGTH 201'-5") x 33'-6" x 15'-11" D. MLD. TO UPPER DECK.

SCALE: 1/2" = 1 FOOT.

TO CLASS 100A.1. LLOYDS 'WITH FREEBOARD' FOR CHANNEL SERVICE.

SUMMER DRAFT: 12'-6" EXTREME.

## LLOYDS NUMERALS.

BREADTH 33.5  
DEPTH 15.92  
B+D = 49.42  
LENGTH = 201.5  
Lx(B+D) = 9974.25  
LxD = 3224.32  
L/D = 12.65  
d = 7.33  
d (WHERE NO 2ND D.K.) 14.50



## SECTION THRO DOUBLE BOTTOM UNDER ENGINES.

MARGIN PLATE 36  
MARGIN ANGLE 3x3x36

FLOORS 30.

CENTRE GIRDER 30"x40"

TOP ANGLES 3x3x38 DOUBLE  
BOTTOM ANGLES 3 1/2x3 1/2x40 DOUBLE  
VERTICAL ANGLES 3x3x40 DOUBLE

TANK TOP PLATING 36.

## RIVETING TABLE.

SEAMS OF SHELL PLATING FROM KEEL TO UPPER TURN OF BILGE DOUBLE RIVETED  
SEAMS OF SHELL PLATING FROM UPPER TURN OF BILGE TO BRIDGE PL SINGLE RIVETED  
EXCEPT FOR SHEERSTAKE AT EACH END OF BRIDGE WHICH ARE DOUBLE RIVETED  
END LAPS OF KEEL TREBLE RIVETED THROUGHOUT  
SEAMS OF KEEL DOUBLE RIVETED ALL FORE & AFT  
END LAPS OF CENTRE KEELSON & RIDER PL. TREBLE RIVETED FOR 1/2 L. TO DOUBLE AT ENDS  
END LAPS OF BRIDGE PL STRINGER DOUBLE RIVETED FOR 1/2 LENGTH TO SINGLE AT ENDS  
END LAPS OF UPPER PL STRINGER DOUBLE RIVETED IN BRIDGE & AT ENDS TREBLE IN WAY OF GANGWAYS  
END LAPS OF 2ND PL STRINGER DOUBLE RIVETED ALL FORE & AFT  
SEAMS OF PL PLATING SINGLE RIVETED THROUGHOUT  
SEAMS OF TANK TOP PLATING IN E.R. SINGLE RIVETED  
END LAPS OF TANK TOP PLATING IN E.R. DOUBLE RIVETED




Two B.  
Each M  
Per Lo  
To S.P.  
301

1. ... ..

S. S. Roebuck.  
NEWCASTLE ON TYNE.  
Report No. 79153.

003808-003815-0230



© 2020  
Lloyd's Register  
Foundation



Swan & Hunter.

No 1204 & 1206

No 2

Midship Section.

No 2

S.S. SAMBUR.

NEWCASTLE ON TYNE.

Report No. 179198

Reback

RETAIN

003808-003815-0230



© 2020

Lloyd's Register  
Foundation