

Lloyd's Register of Shipping.

Ship's Name "OLWEN"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Extract from Port Natal Report Number 4293 dated June 1944.

At the owners desire the following repairs and alterations were carried out.

Bridge deck housing cropped at bottom and part renewed together with deck angles.

Bridge steel and wood deck renewed. Poop deck housing cropped at bottom and part renewed together with foundation angles. Poop deck and housing extended to cover tween deck openings 3rd from aft (P & S) the coamings were removed. Poop superstructure bulkhead, new opening cut (p.s) 5' x 3' with 2' sill and fitted with strongly constructed steel watertight door which can be operated from both sides. Wood boat deck on poop (p & s) renewed and laid on new steel deck.

Forecastle superstructure deck renewed. Forecastle tween deck except stringer plates renewed. Fore and Aft gangway all wood deck and guard wires renewed. A new gangway of similar construction to F.A. gangway was laid from poop to forecastle (ss) and from poop to bridge (ps).

N.B.
23-10-44

