

# Lloyd's Register of Shipping.

Ship's Name RADANAOfficial No. 167247

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Vessel has now been converted into a Merchant Aircraft Carrier.

The hatch to the Fore Hold on Forecastle Deck has now been plated over and 3 small latches fitted in plating each 2'-6" x 2'-6" x 6" boaming with wpt. steel plate cover secured by wing nuts and bolts.

## VENTILATORS. FORECASTLE DECK.

Additional Ventilators fitted. 1 @ 13" dia. boaming 30" x 34".  
 1 @ 12" " " 36" x 32".  
 5 @ 10" " " 36" x 32".  
 5 Gonnecks 5" dia 35" high to top.  
 Ventilators removed 9 @ 6" dia.

BRIDGE DECK. Additional Ventilators fitted 3 @ 6" dia. boaming 30" x 32".

1 Gonneck 5" dia - 36" high to top.

POOP DECK. Additional Ventilators fitted. 2 @ 9" dia. boaming 30" x 32".  
 9 Gonnecks 5" dia. 30" to top.  
 Vents removed. 5 @ 12" - 5 @ 8" - 2 @ 10" dia.

All Vents closed with wood plugs and canvas covers.

## SCUPPERS & SANITARY DISCHARGES.

Discharges from Accommodation in Forecastle now removed and holes in shell blanked off.

BRIDGE SPACE Additional Sanitary Discharges PORT 1'-2 1/2" dia. 1'-2" dia.  
STARBOARD 1'-3" dia. 2'-2 1/2" dia.

Discharges fitted above Foreboard Deck and fitted with Storm Valves.

POOP SPACE Additional Sanitary Discharges. PORT 2'-2" Dia:

Discharges fitted below Foreboard Deck and fitted with Storm Valves.

## FREEDING ARRANGEMENTS.

AFT WELL. Length of Bulwarks 113'-0".

Height of Bulwarks 3'-7" to 4'-9".

Total Area of Freeing Ports 41.5 sq.

Freeing Ports from 11" to 21" above Deck.

Freeing Ports fitted with Vertical Rails 1" dia.

OPEN RAILS. 45'-0"

FORW. WELL. Length of Bulwarks 84'-6"

Height of Bulwarks 3'-7" to 4'-9"

Total Area of Freeing Ports 25.2 sq.

Freeing Ports from 12" to 18" above Deck.

" " fitted with Vertical Rails 1" dia.

OPEN RAILS. 30'-6"

The Exposed Machinery Casings on Poop Deck have now been enclosed at Side (P&S) with Accommodation Deckhouse.

## PARTICULARS OF CLOSING APPLIANCES

Forecastle Front. 4 wood lugged doors have now been removed and openings plated over.