

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) M.K.M.M.

Official Number.	Name of Ship.	No., Date, and Port of Registry.		
160,775.	"Boltonhall"	4/1935 West Hartlepool.		
No., Date, and Port of Previous Registry (if any). Nil.				
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Screw.	West Hartlepool.	1935	Messrs. Wm. Gray & Co., Ltd., West Hartlepool.
Number of Decks . One & Shelter Deck with Forecastle.		Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet. 410	Tenths. 7
Number of Masts Two		Length at quarter of depth from top of weather deck at side amidships to bottom of keel	407	6
Rigged Fore & Aft.		Main breadth to outside of plank	54	8
Stern Elliptical		Depth in hold from tonnage deck to ceiling at midships.. ..	24	9
Build Clincher		Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards.. .. .	--	--
Galleries -----		Depth from top of beam amidships to top of keel	28	7
Head -----		Depth from top of deck at side amidships to bottom of keel	27	8.1
Framework and description of Steel Cargo vessel		Round of beam	1	1.25
Number of Bulkheads .. 6 watertight		Length of engine room, if any	49	
Number of water ballast tanks, and their capacity in tons 1 gas tight				
9. total 2541 tons				

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel. 9810 Tons. Ditto per inch immersion at same depth 43.7 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Reciprocating Inverted Direct Acting "Quadropod" Type.	Engines. British	Engines. 1935	Engines. and	four 18 1/2" 25 1/2" 41" 61"	48"	----	468
No. of Shafts.	Particulars of Boilers.							
	Description Cyld. Mul. S.E.	Boilers. British	Boilers. 1935	Boilers. Central Marine Engine Works of Messrs. Wm. Gray & Co., Ltd.,				2330
One	Number Three							
	Iron or Steel Steel							
	Loaded Pressure 260 lbs.							11 Knots

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	4377.76	On account of space required for propelling power	1543.84
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	253.13
Turret or Trunk	17.54	These spaces are the following, viz. :—	
Forecastle	22.22	Poop and Round House	
Bridge space Upper Forecastle Houses	11.12	(Number of Seamen or Apprentices for whom accommodation is certified. 43.....).	
Poop or Break	134.27	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—	
Side Houses	242.87	Master's Accom. 23.00	
Deck Houses		Chart Space 3.94	
Chart House	18.72	Wireless Tel. Sp. 2.33	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		Boatswains Store 41.56	166.95
Excess of Hatchways		Fore Peak 52.50	
		Aft Peak 43.62	
Gross Tonnage	4824.50	Cubic Metres. 13653.34	
Deductions, as per Contra.	1963.92	5557.90	
Register Tonnage	2860.58	8095.44	1963.92

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 614.61 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 134.72 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle Length 25 feet 49.97 tons.
Tween Decks I Length 182.1 ft. - 673.57 tons. II Length 49 ft - 145.12 tons.
III Length 113.6 ft - 457.79 tons IV Length 5.1 ft. - 20.26 tons.

Name of Master	--- Ernest Moller----	Certificate of	{ Service Competency	No. No. 003760
No. of Owners				
Name, Residence, and Description of Managing Owner if there are more owners than one.	The Wiltonhall Steamship Company Limited. 38, Church Street, West Hartlepool, Durham. Julius Ernst Guthe same address-Manager-.			
Dated	11th December 1935.			



Sixty-four (64) Shares.

© 2020

Lloyd's Register Foundation

003832-003837-0058