

9 FEB 1948

Rpt. C. 11 (Contd.)

Index No. ....

# Lloyd's Register of Shipping.

Ship's Name "MERCHANT KNIGHT" s.s. "BOLTON HALL" Official No. 160775

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in Reversion to open shelter deck.

Tonnage opening: Steel cover removed, and 3" wood covers fitted ✓  
Guard Rails & stanchions fitted

Scupper: 6" x 4" S.M. gale Valve overhauled & fitted in tonnage well P+S  
for drainage of this space, Valve spindles overhauled & fitted,  
extending to weather deck, and fitted with indicators to show  
when open or shut. See Hull Rpt C.11 (Contd.) May 1946.

Scupper: Amidsheeps within bridge space draining to boiler & machinery  
spaces, previously fitted at (Hull May 1946.) overhauled & placed  
in good condition. self closing cocks fitted at the lower  
ends of scupper.

Bridge end B<sup>HD</sup>: Fitted with 3" shifting boards in full height  
ruled channels.

Second D<sup>th</sup>: Hatch covers, cleats & battens bars renewed as required  
wedges & lashings supplied ✓

Escape hatches: Covers & fastenings renewed as required ✓

Copy placed in bound. ✓

N. D. Johnston  
W. H. P. January 1948.

W. H. P.  
JAN 1948

10 FEB 1948

