

Lloyd's Register of Shipping.

Ship's Name BOLTON HALLOfficial No. 160775

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 12/1935

The following alterations have now been effected consequent upon closing the tonnage opening in shelter deck.

- ① Tonnage opening in the shelter deck has been permanently closed by welding a plate at top of bulb angle coaming, & companion way fitted in tonnage opening top. Keeling ports in tonnage well permanently closed by welding in place.
all overboard scuppers from the shelter tween decks including tonnage well, permanently closed by welding plates over shell and deck openings.
- ② Sanitary discharge from gunners accommodation on Starb Side of shelter tween decks space, aft, fitted with screw down automatic non-return valve, controlled from the shelter deck, side light fitted in ship's side with dead light.
- ③ Suitable provision has been made for rigging life lines forward and aft by fitting eye plates on deckhouses and lifelines supplied.
- ④ The shelter tween deck space has been efficiently drained to the bilges by fitting two scuppers each side.

The watertight bulkheads have not been extended to the shelter deck.

Load line Survey carried out.

The freeboard marks have been altered and the deck line cut in at the top of shelter steel deck in accordance with assignment note.

A copy of this memorandum has been forwarded to the owners to be placed on board the ship.

L4-0-0 (a/c 28 MAY 1941)

Noted
RJB

30 MAY 1941

Ch. Swan

14th May 1941