

WALKER, CRUMP & Co.,

CONSULTING MARINE SURVEYORS.
ENGINEERS & NAVAL ARCHITECTS.

DENNIS C. CRUMP,

F.C.M.S., M.I.N.A., M.N.E.C.INST., M.I.MAR.E.

ARCHIBALD WALKER,

M.A., F.C.M.S., M.INST.C.E., M.I.N.A., M.I.MAR.E.

TELEGRAPHIC ADDRESS:

"WATERFRONT, FEN, LONDON."

TELEPHONES: AVENUE 5921-1408

(AFTER OFFICE HOURS—SEVEN KINGS 2089)

PRIVATE TELEPHONES:

MR. CRUMP—SANDERSTEAD 3184

MR. WALKER—HORSHAM 659

Principal Surveyor,
Lloyds Register of Shipping,
Salvage Buildings,
Clarence Road,
CARDIFF.

1/3 Mount Stuart Square,

CARDIFF.

~~246 LEADENHALL HOUSE,~~

~~101 LEADENHALL STREET,~~

~~LONDON, E.C.3.~~

JLH/MB

July 31st 1948

Dear Sirs,

M.V. "GOLDFINDER"


Further to our conversation of the 29th instant we now enclose diagrammatical sketch in connection with the proposed use of the after peak of the above vessel as a bunker tank on the voyage U.K. to New Zealand.

Subject to your approval we propose to have the tank tested, scaled, cleaned and internally examined, the ballast suction line fitted with a blank flange, the end of the air pipe fitted with a bell mouth and gauze wire and a new filling pipe installed, the manhole door rejointed with oil tight jointing and a new suction line with a semi rotary hand pump from the peak to the ready use tank.

We shall be glad to have your approval of this proposal at your earliest convenience.

Yours faithfully,

for WALKER, CRUMP & CO.,



Encl.2 diagrammatical sketches.



© 2021

Lloyd's Register
Foundation

003838-003843-0109