


COPY

# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER



Port Willemstad, Curacao N.A.

28th March 1957.

This is to Certify that

W. S. Holness

the undersigned Surveyor to this Society did at the request of Owners Representative attended on board the M.V. "LUCIA" 3217 Tons Gross of Willemstad, a float at Curacao N.A. on 25th March 1957 and subsequently, in order to ascertain nature and extent of damage stated to have been sustained due to contact with "Palmarejo" dolphin, Lake Maracaibo, Venezuela whilst berthing in ballast condition, on 22nd March 1957.

For further particulars please see vessel's Log Books.

Upon examination the Undersigned:-

FOUND

Damage confined to bow plating port side:

1st plate from stem, port side, in 2nd strake below main sheer strake set in and holed over length of approx. 4'0".

One longitudinal frame buckled over approx. length of 4'0".

One breast hook buckled.

RECOMMENDED

To be renewed.

To be cropped and part renewed.

To be renewed.

The above recommendations have been made in order to place the vessel in as good a condition as she was in before the alleged casualty, and have been deferred until next Drydocking, but in the meantime, and as a temporary measure a doubling plate 4'6" x 4'0" x 3/8" welded over holed plate, examined and hose tested upon completion and found satisfactory in the meantime.

*W. S. Holness*

Surveyor to Lloyd's Register  
of Shipping, Curacao N.A.

Fee & Expenses: -fls. 160.00

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."