

Lloyd's Register of Shipping.

Ship's Name S.S. **YEWFOREST**Official No. **180495**

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in **GREENOCK REPT N^o. 23520**

Permanent chain attachment provided for flush bunker scuttle cover.

Hatch on casing top 3'-6" x 2'-0" - Coaming 4" x 30" efficient hinged steel cover secured by toggles.

Companionway sill on bridge deck now 18" high.

Special lashings & ring bolts are provided for N^o 1 hatchway

Sanitary sink drainage from poop space, & sanitary sink & drainage from bridge space discharge through shell above gunboard deck and are fitted with automatic non-return valves at shell.

The companionway doors are capable of being operated from both sides.

MLD

003846-003857-0041

© 2020
Lloyd's Register
Foundation
Alfred Corbett
noted. 
13 JUL 1947
16/7/47