

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name *"PERELLE"* Official No. *180995*Port of Registry *Glasgow*

This ship has been under survey at

*South Shields**between the 16th August & 16th September*

OR

1955 and the following alterations to the conditions of

assignment of loadlines have now been effected/~~made~~:-

The following alterations have now been effected in conjunction with the fitting of a new water ballast tank in engine room and Poop Tween decks, also the converting of No 3 Double bottom tank from oil fuel to water ballast.

Poop Tween deck Ballast tank:-

Stark Bunkers scuttle on Poop deck aft now dispensed with and replaced by a circular hatch 18 1/2" Diameter having a steel coaming 18" high and provided with a hinged steel watertight cover in accordance with rule requirements.

Additional air pipes now provided:-

*Poop Tween deck Ballast tank :: 1 Port & 1 Starb at 3" Diameter. } ON POOP DECK.
 Engine Room Ballast tank :: 1 Port & 1 Starb at 3" Diameter. } 30" IN HT.*

The foregoing air pipes have been provided with a wood plug.

The original air pipe to No 3 DB tank has this gauge removed and wood plugs provided.

M. Donaldson.

20 OCT 1955

A copy of this report has been forwarded to the agents to be placed on board the vessel at the earliest opportunity.

A copy of this Report has been placed on board.

Submitted the Surveyor be requested
to report height ^{additional} of air pipes & their
position.

DPR. 13 OCT 1955



© 2020

Lloyd's Register
Foundation