

ITEM	RULE SCANTLING	AMENDED SCANTLING
CENTRE GIRDER PLATE	52	78
CENTRE GIRDER TOP ANGLE	3 . 3 . 50	4 . 4 . 75
" " BOTTOM ANGLE	3 1/2 . 3 1/2 . 42	4 . 4 . 64
" " VERTICAL ANGLES	3 . 3 . 42	4 . 4 . 60
TANK FLOORS PLATES	42	60
TANK INTERCOSTAL PLATES	42	60
TANK INTERCOSTAL TOP VERT ANGLES	3 . 3 . 42	4 . 4 . 60
TANK INTERCOSTAL BOTTOM ANGLES	3 . 3 . 42	3 1/2 . 3 . 42
TANK MARGIN PLATE	46	70
MARGIN SHELL ANGLES	3 . 3 . 40	4 . 4 . 60
MARGIN VERTICAL ANGLES	3 . 3 . 40	4 . 4 . 60
TANK WING BRACKETS	44	60
MIDDLE LINE STRAKE OF		
TANK TOP PLATING	48	70
TANK TOP PLATING	48	70
TANK FRAMES	3 . 3 . 32	3 . 3 . 42
TANK REVERSE FRAMES	3 . 3 . 42	4 . 4 . 60

MIDSHIP SECTION

DIMENSIONS 213'-0" B.P. x 35'-6" MOULDED x 13'-9" TO LOWER DECK & 21'-9" TO UPPER DK.

TO CLASS LLOYD'S 100 A.I. WITH FREEBOARD CORRESPONDING TO A
MEAN DRAFT OF 13'5" MOULDED.

2 IN WAY OF BOILER ROOM, WHERE NO SIDE STRINGER = 19

3 BOWER ANCHORS, EACH 25 1/2 CWTs. STOCKLESS = 76 1/2 CWTs.
1 STREAM ANCHOR 6 1/2 CWTs. EX. STOCK.
210 FATHOMS 1 1/8" STUD LINK CHAIN CABLE ("BEST BEST" OWNERS REQ.)
75 -do- 1 5/16" STREAM CHAIN.
90 -do- 3 1/4" STEEL WIRE TOWLINE ON REEL.
90 -do- 2 1/4" STEEL WIRE WARP ON REEL.
90 -do- 5" MANILLA WARP.

KINETING		FOR 1/2 L	ATENOS
BUTT KINETING		DOUBLE LAPS	DOUBLE LAPS
BRIDGE DECK SHEERSTRAKE		TREBLE LAPS	DOUBLE LAPS
UPPER		DOUBLE LAPS	DOUBLE LAPS
BRIDGE DECK STRAKE BELOW SHEERSTRAKE		DOUBLE LAPS	DOUBLE LAPS
UPPER		TREBLE LAPS	TREBLE LAPS
KEEL STRAKE		TREBLE LAPS	DOUBLE LAPS
SHELL PLATING TO UPPER TURN OF BILGE		DOUBLE LAPS	DOUBLE LAPS
FROM UPPER TURN OF BILGE TO STRAKE BELOW SHEER		TREBLE LAPS	TREBLE LAPS
BO 33 PLATES			
BRIDGE DECK STRINGER PLATE		DOUBLE LAPS	
UPPER		DOUBLE LAPS	DOUBLE LAPS
LOWER		DOUBLE LAPS	DOUBLE LAPS
BRIDGE DECK TIE PLATES		DOUBLE LAPS	
UPPER DECK PLATING		DOUBLE LAPS	SINGLE LAPS
LOWER		DOUBLE LAPS	SINGLE LAPS
CENTRE GIRDER		TREBLE LAPS	DOUBLE LAPS
MARGIN PLATE		DOUBLE LAPS	DOUBLE LAPS
MIDDLE LINE STRAKE OF INNER BOTTOM		DOUBLE LAPS	DOUBLE LAPS
INNER BOTTOM PLATING		DOUBLE LAPS	SINGLE LAPS
EDGE KINETING			
SHEERSTRAKE & STRAKE BELOW		DOUBLE LAPS	
GARBBOARD STRAKE		DOUBLE LAPS	
PLATING BELOW UPPER TURN OF BILGE		DOUBLE LAPS	
PLATING ABOVE		SINGLE LAPS	
DECK STRINGERS & PLATING		SINGLE LAPS	
INNER BOTTOM PLATING		SINGLE LAPS	

SECTION THREE HOLDS

S/S "FALCON"

MIDSHIP SECTION (AS BUILT)

Nov. 1927.

GLASGOW REPORT No 47325

RETAIN



© 2020

Lloyd's Register
Foundation

003884-003894-0070