

5c.11.41

R

Blyth Dry Docks & Shipbuilding Co.Ltd., Blyth.

Yard No.313.

F.E.
(FBD.)

"B" Type S.E.A.C. coasting vessel and sister ship to the
"EMPIRE PAVILION" etc.

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME s.s. "EMPIRE PASSMORE" REPORT Nwc. No. 103518

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

D to Sh. dk 21.66'. D to 2nd dk 14.08'. D for scantlings 21.58' (i.e. 7.5' above
 1st Long. No. 4532 Depth "d" 11.38 2nd dk).
 2nd Long. No. 12197 Proportions = $\frac{L}{D}$ 9.6
 Framing Bulb angle frames as approved Sheerstrake As approved

This is a C.S.S. vessel with tonnage opening.

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed ~~100A1~~ "With freeboard" "Fitted for oil fuel 2.46, F.P. above 150°F"

The Summer Freeboard as shown on the attached extract from the Freeboard Verification Form, now marked on the vessel's sides, to be inserted in the classification certificate and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying extract, to be inserted in the certificate of classification.

1 Dk & Shelter dk.
 Cell DB 144' 246t, DTf 6' 77t, FPTs 69t, APT 22t
 FK, 4BH (2 to Sh. dk, 2 to 2nd dk), Lloyd's A & CP
 F 30'
 Mchy Aft
 O.L. 224.4'
 Extreme breadth over belting 38.0'
 "n"



It is submitted the Surveyors be requested to furnish the scantlings of the foundation plates on the centre keelson in way of the engine room and the width of the ~~Shelter~~ and 2nd deck stringer plates, which have been omitted from their report.



© 2020

Lloyd's Register
 Foundation

003884-003894-0342