

LLOYD'S CLASS 100 A1 +.

LENGTH BETWEEN LLOYD'S PERP.	=	242'-0"
BREADTH MOULED	=	38'-0"
DEPTH	=	18'-0"
LENGTH OF POB	=	65'-2"
" " RAISED QUARTER DECK	=	70'-8"
" " FOLE	=	29'-0"
HEIGHT " POB	=	4'-3"
" " RAISED QUARTER DECK	=	4'-0"

$L \times (B+D) (D)$  TO MAIN DECK = 13552  
 $L \times B$  " " " = 4356  
 $\frac{L}{D}$  " " " = 13.44  
 $\frac{L}{B}$  " " R. Q. D. = 11  
 $D = 10'$ ,  $d = 15' - 3"$

RQD at 19'-3"

POOP	65'-2" x 7'-6" x 0.75	=	366.56	367	✓
FOLGE	29'-0" x 7'-3" x 0.75	=	157.60	158	✓
R.Q. D.	78'-7" x 4'-0" <del>x 0.50</del>	=	157.16	314	✓
CRIBS AND CASING	14'-0" x 6" x 0.50	=	151.04	206	✓
SALOON	9'-7" x 10'-0" x 0.50	=	47.91	48	✓
PLATING NUMBER		=	13551	13552	
			14433.18	14464.5	

FORCASTLE DECK  
STRINGER PL: 0" BUTTS LAPP: DOUBLE RIV:  
" ANGL 3"x3"x.30"  
DECK PL: .26" BTTS LAPP: SINGLE RIV:  
BEAMS ON EVERY FRAME 6"x3"x.36" F (150"x70"x9 1/4")  
RIV: 5/8"  
WOOD SHEETIN 2 1/2" P. PINE

POOP DECK  
STRINGER PL. .29" BUTTS LAP: DOUBLE RIV: 5/8"  
" RANGLE 3"x3"x.29"  
DECK PL. .16" BUTTS LAP: SINGLE RIV: 5/8"  
BEAMS ON EVERY FRAME 5/8"x3"x.34" F  
HALF " " " " 5/8"x3"x.34" L  
THROUGH BEAMS SEE PROFILE  
WOOD SHEETING 1 1/2" P. PINE

SCHAAL  $\frac{1}{2}'' = 1'$

SECTION THROUGH TRUNK BETWEEN  
AND AT ENDS OF MATCHES.

POOP DECK

A hand-drawn diagram of a ship's hull section. It shows a cross-section of the hull with a gunwale bar. A shear stroke is indicated by a line across the gunwale bar. A scupper is shown as a hole in the gunwale bar. A joint piece is shown as a separate piece of wood. The diagram is labeled with the following text:

- SHEAR STROKE
- SCUPPER
- GUNWALE BAR
- JOINT PIECE

Handwritten notes in red ink are also present:

- Only at RED
- not at upper

GESCHIEDENIS WERF  
VOORHEEN  
JAN SMIT CZ.

PLASSERDAM

100

ANCHORS AND CHAINS		
1 STOCKLESS BOWER	29 CWT.	} 87
1 "	29 "	
1 "	29 "	
1 STREAM ANCHOR	7 1/2 "	
1 1/2" STUD CHAIN CABLE	140 FATHOM.	


18" x 13" x .36"  
Knees at Parting Frames to be  
suitable for  $\frac{1}{4}$  -  $\frac{3}{4}$  R's

[illegible][illegible]

1.2.'27

EM

003895-003905-0128



© 2020  
Lloyd's Register  
Foundation



Messrs Jan Smit & Co.  
No 498


Midship Section

~~GEN BOX NO 720~~

Queensland &  
Beijerland<sup>esc</sup>

Rot Rpt 17214

S/R.I.



© 2020

003895-003905-0128  
Lloyd's Register  
Foundation