

4

## LLOYD'S REGISTER OF SHIPPING,

810 HENNER BUILDING,

NEW ORLEANS, LA.,

J. M. BUCHANAN,  
AND ENGINEER SURVEYOR.LLOYD'S REGISTER OF SHIPPING  
NEW YORK  
Oct: 30th. 1918.

REC'D NOV 2 - 1918

ANS'D \_\_\_\_\_

The Secretary,

New York,

Dear Sir,

"MEXOIL"

I am in receipt of your letter of the 21st: inst: regarding this new Steamer, and in reply, the rudder head or stock is 6 1/2" diam.:, the stiffening of collision and longitudinal bulkheads is in accordance with the approved plans, and as required, the single angle connecting girder to bottom transverses is 5" x 5", and the sheerstrake is increased in thickness at the break of poop, the thickness being 13/16"; The only tie plates on poop deck are in way of deck houses, and are 9" x 5/16", besides the deck stringer plate; The pillars in forehold, one pillar under after end of hatch coaming, two channels back to back 10"x3 1/2" x 9/16"; In similar cases I shall include these particulars in my Report.

I am,

Yours faithfully



© 2020

Lloyd's Register  
Foundation

003895-003905-0165

