

# Lloyd's Register of Shipping.

Ship's Name "MYRTLEBANK"

Official No. 148885

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

In after bridge bulkhead the weather boards on port side opening have been replaced by a hinged wood door to provide access to gunners accommodation which has been fitted right across the ship at aft end of shelter tween deck.

The starboard opening has been left open to provide emergency exit to stairway. Sidelights with hinged D.Ls fitted in accommodation.

Sanitary discharges overboard fitted with storm valves above freeboard deck.

Tonnage opening in shelter deck permanently closed by plating over with 4 f and a beams. Steel companion fitted with 20" sill and wood door operated both sides.

Port trimming hatch in accommodation removed and hole plated over.

This hatch coaming fitted on tonnage opening as an ammunition hatch with battens, cleats, wood cover and tarpaulins, height 18". Steel magazine fitted in cr. of tonnage well. Loadline certs amended to agree with the above alterations.

(Sgd.) Arthur N. Smith.

LONDON.

30th May, 1941.

*Noted PWB  
576/41*

