

To go with big Rpt. LONDON

COPY

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER



Port CALCUTTA

15th January, 1960.

This is to Certify that

A. McCOURTS.

the undersigned Surveyor to this Society did at the request of

Messrs. Gladstone Lyall & Co. Ltd. Lloyd's Agents, Calcutta and on behalf of the Salvage Association, London, survey the M.V. "YENANGYAUNG" 5938 tons gross of London on the 23rd December 1959 and subsequently whilst the ship was afloat at Kidderpore Dock, Calcutta for the purpose of ascertaining the nature and extent of damage stated to have been caused by propeller striking a buoy on the 23rd December 1959 at Calcutta whilst vessel was undocking at Kidderpore Dry Dock.

For further particulars see Log Books.

The undersigned upon examination with vessel afloat.

FOUND

1st Propeller blade portion approximately 6" deep extending from leading edge to propeller tip missing.

2nd Propeller blade, minor serrations on tip.

3rd Propeller blade, approximately 6" of tip for a length of 24" bent over at right angles to plane of propeller blade.

4th Propeller blade, approximately 3" of tip for a length of 24" bent over at right angles to plane of propeller blade and slightly torn.

RECOMMENDED

Temporary Repair.
Damaged portion to dress.
Permanent Repair.
Profile to restore.

Temporary Repair.
Damage portion to dress.
Permanent Repair.
Profile to restore.

Temporary Repair.
Damaged tip to crop and dress up.
Permanent Repair.
Profile to restore.

Temporary Repairs.
Damaged tip to crop and dress up.
Permanent Repairs.
Profile to restore.

A. McCourts 12...

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—
"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers Agents of the Society."

Lloyd's Register Foundation
003937-003947-0220 1/2


COPY

Lloyd's Register of Shipping.

- 2 -

M.V. "YENANGYAUNG"

The above recommendations have been made in order to place the ship in as good a condition as she was in before the alleged casualty, and the temporary repairs have been carried out to my satisfaction and the permanent repairs have been deferred until convenient to the Owners.



SURVEYOR TO LLOYDS REGISTER OF SHIPPING.



© 2020

Lloyd's Register
Foundation

0220 2/2