

14 FEB 1965

Ship's name NAN AN.

Port Kobe

No. 13754

Class is subject to NIL.

Last survey date 12.12.64

Locking - wear down 4 mm.

TS due 4.66 - now held

Damage to propeller, cause unknown, TS drawn at request of Owners.

Propeller blades slightly bent at leading edges - now repaired. TS found cracked at base of cone - depth 2.7 mm. Crack ground out & shaft crack detected. Surveyor recommends that the base of the tail shaft cone be crack detected by 12.65.

(Surveyor reports spare TS crack detected & found cracked in way of keyway. Shaft now condemned & marks obliterated)

It is submitted that this vessel is eligible for THE RECORD.

& crack detection.

TS (CL) 12.64 subject to base of tail shaft cone being specially examined by 12.65 (12 mos). TS record of 12.64 withheld meantime.

Boyd's Register Foundation
65