

5c.10.40.

1 (5.)

Lithgow's Ltd.

Yard No. 972.

"Y3" type.

Lameyton Grange

Sent to Chief Surveyors.....

Received from Chief Surveyors.....

VESSEL'S NAME. s.s. "EMPIRE PENNANT" Report Grk. No. 22115

For the CHIEF SHIP SURVEYOR and CHIEF ENGINEER SURVEYOR.

(In cases which have to be submitted to the Classing Committee "the endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Nature of Survey..... First Entry..... When due=

This is a sister vessel to the "EMPIRE LANCER" etc.

The scantlings are suitable for a draught of 18" in excess of that corresponding to the freeboard which could be assigned as a C.S.S. vessel.

The tank top plating has been increased in thickness under the hatchways in lieu of ceiling.

Nos. 2 & 4 holds and 'tween decks have been insulated.

100 Al With freeboard.

2 Dks

Cell DB 370' 1215t, FPT 122t, APT 172t

FK, 7BH (Coll to W dk, 6 to 2nd dk), 5 divisional W.T. BHs in 'tween dks.,
pt. Cem., Lloyd's A & CP

F 39'

O.L. 447.6'

a⁺


The class is assigned and maintained upon the understanding that the equipment will be made to accord with the requirements of the Rules when the present state of emergency has passed, and that hatch covers at the 2nd deck at Nos 1 & 6 hatchways and cargo battens in uninsulated cargo spaces will be fitted at the first available opportunity.

Insert in S.R.L.:-

(A bower anchor and 45 fathoms of chain cable to be supplied).

Hatch covers at 2nd deck at Nos. 1 & 6 hatchways and cargo battens in uninsulated cargo spaces to be fitted at the first opportunity.

NOTE: The fitting of an Echo sounding device has not been completed.



© 2021

Lloyd's Register Foundation

003971-003979-0050

Poop Deck, Angle, ☐ or ☐

Angles