

COPY.


G.2328.

Lloyd's Register of Shipping.



Port BIRMINGHAM.

29th. October, 1942.



This is to Certify that

E. McCRIBICK

the undersigned Surveyor to this Society did at the request of

Messrs. Belliss & Morcom Ltd., Ledsam Street, Birmingham, attend at their Works on the 19th. October, 1942 and subsequently for the purpose of witnessing running tests on two 75 H.P. Compound Steam Engines Nos. 9996-7, made to the order of Messrs. J. & E. Hall Ltd., and intended for Messrs. Lithgows Ltd., Ship No. 978.

Each engine consists of cylinders 7" and 11" diameter, stroke 5", running at speeds varying 340-720 R.P.M. using steam at 180 lbs. per square inch and intended for driving refrigerating machinery.

Each engine was submitted to a running test (when coupled to an H. & P. Water Brake) of 3 hours under full load, 1 hour under 3/4 load and 1 hour under 1/2 load, during which period the results were found to be to specification and satisfactory.

Following the trials each engine was opened up for examination and the working parts found to be satisfactory.

The materials and workmanship so far as could be ascertained were good.

For identification purposes the sets were stamped on the engine and casing as follows:-

Engine Nos. 9996	and 9997.
LLOYD'S Nos. 278	" 279.
EMCS. 20/10/42	" 21/10/42.

D. Rowan & Co

E. Pennant

Fee 24. 4. 0.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."