

Capt. Polmiller - Humboldt  
Engineer No. 34741-2-3-4

Spec. 5628

It is submitted the Spec. Surveyors be informed  
with reference to the last paragraph in their  
that whilst it is a requirement <sup>of the Rules</sup> that the  
cylinders of all heavy oil engines should be  
fitted with safety valves, no objection has been  
taken to the omission of such valves on cylinders  
exceeding 150 mm. bore; or in cases of engines  
requiring compressed air for starting, on cylinders  
exceeding 200 mm. bore.

In the present case the cylinders are  
mm. bore, and the Surveyors should be  
requested to take up the matter with the  
makers, unless they can quote the  
lifting of a previous concession.

Wm. Stew 9/7/43

Lloyd's Register  
Foundation

9550-616500-46500  
003491-003979-0256