

Lloyd's Register of Shipping.

Ship's Name "WIMBLEDON"

Official No. 166330

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

A Brompton type ash hoist and ash shoot has now been fitted at raised quarter deck on Starbd. side abreast the machinery casing and led overboard through ship's side. The hoist is strongly constructed, and above the raised quarter deck is fitted with a W.T. door of steel having a sill 18" high above deck.

The ash shoot was satisfactorily water tested.


The side shell plating in way of shoot was suitably compensated.

The wood doors of the emergency escape from the engine room on the casing top have now been replaced by an ^{W.T.} steel door capable of being operated from both sides.

A copy of the above has been placed on board ship.

H. Little
Lloyd's Register of Shipping
16/8/49

23 AUG 1949



© 2020

Lloyd's Register
Foundation