

REPORT ON ELECTRICAL EQUIPMENT.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office

JUN 10 1930

Date of writing Report 1 June 1930 When handed in at Local Office 19 Port of Amsterdam
 No. in Survey held at Amsterdam Date, First Survey 8 March Last Survey 24 May 1930
 Reg. Book. on the Single Screw M.V. "CARELIA" (Number of Visits 15) Tons { Gross 8033
 Net 4729
 Built at Amsterdam By whom built N.V. Nederl. Scheepb. 14 Yard No. 266 When built 1930
 Owners N.V. Petroleum N^o "La Carma" Port belonging to 's Gravenhage
 Electric Light Installation fitted by N.V. Groeneveld & d. Polak & Co Contract No. When fitted 1930
 Is the Vessel fitted for carrying Petroleum in bulk Yes

System of Distribution Double wire ✓
 Pressure of supply for Lighting 110 volts, Heating ✓ volts, Power 110 volts.
 Direct or Alternating Current, Lighting Direct current Power Direct current
 If alternating current system, state frequency of periods per second ✓
 Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes
 Generators, do they comply with the requirements regarding temperature rise Yes, are they compound wound Yes
 are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator ✓
 Where more than one generator is fitted are they arranged to run in parallel no, is an adjustable regulating resistance fitted in series with each shunt field Yes
 approved attached Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing ✓
 Have certificates for generators under 100 kw. been supplied and approved ✓
 Are all terminals accessible, clearly marked, and furnished with sockets Yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes
 Position of Generators Motorroom on SB side
 in way of the generators satisfactory Yes are they clear of all inflammable material Yes if situated near unprotected
 woodwork or other combustible material, state distance of same horizontally from or vertically above the generators none and ✓
 are the generators protected from mechanical injury and damage from water, steam or oil Yes, are their axes of rotation fore and aft Yes
 Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes are the prime movers and their respective generators in metallic contact Yes
 Main Switch Boards, where placed Engine room on SB side
 If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard ✓
 Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes, are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards none and ✓, are they constructed wholly of durable, non-ignitable non-absorbent materials Yes, is all insulation of high dielectric strength and of permanently high insulation resistance Yes
 is it of an approved type Yes, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework ✓, is the non-hygroscopic insulating material of an approved type ✓, and is the frame effectively earthed Yes
 Are the fittings as per Rule regarding:— spacing or shielding of live parts, accessibility of all parts Yes, absence of fuses on back of board Yes, temperature rise of omnibus bars 1°C, individual fuses to voltmeter, pilot or earth lamp Yes, are moving parts of switches alive in the "off" position no are all screws and nuts securing connections effectively locked Yes are any fuses fitted on the live side of switches no
 Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches Double pole handle switches
 Are turbine driven generators fitted with emergency trip switch as per rule ✓ Are cupboards or compartments containing switchboards composed of fire-resisting material or lined with approved material ✓
 Instruments on main switchboard 2 ammeters 2
 voltmeters ✓ synchronising device for paralleling purposes. For compound machines is the ammeter connected on the opposite pole to equaliser connection
 Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system Two lamps in series connected with the earth
 do these comply with the requirements of the Rules Yes are the fusible cutouts of an approved type Yes have the reversed

current protection devices been tested under working conditions ☒ are all fuses labelled as per rule *yes*

Joint Boxes, Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule *yes*

Cables: Single, twin, concentric, or multicore *diff. types* are the cables insulated and protected as per Tables IV, V, X, XI, XII or XIII of the Rules *yes*

If the cables are insulated otherwise than as per Rule, are they of an approved type ☒ **Fall of Pressure,** state maximum between bus bars and

any point of the installation under maximum load *2 volt for light 5 v for power* **Cable Sockets,** are the ends of all cables having a sectional

area of 0.04 square inch and above provided with soldering sockets *yes* **Paper Insulated and Varnished Cambric Insulated Cables,**

If conductors are paper or varnished cambric insulated, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with

insulating compound *none*, or waterproof insulating tape ☒ **Cable Runs,** are the cables fixed as far as possible in accessible positions

not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical

damage *yes* are cables laid under machines or floorplates *yes* if so, are they adequately protected *yes*

Are cables in machinery spaces, galleys, laundries, bathrooms and lavatories lead covered or run in conduit *yes* *lead covered & surrounded*

Support and Protection of Cables, state how the cables are supported and protected *galvanised iron clips & brass screws*

If cables are run in wood casings, are the casings and caps secured by screws *yes*, are the cap screws of brass *yes*, are the cables run in

separate grooves *yes* If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *yes*

Refrigerated Chambers, are the cables and fittings in accordance with the special requirements *yes*

Joints in Cables, state if any, and how made, insulated, and protected *no joints*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands

watertight bushes **Bushes in Beams and Non-watertight Partitions,** where unarmoured cables pass through beams and non-watertight partitions, are the

holes efficiently bushed *yes* state the material of which the bushes are made *lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas ☒

are their connections made as per Rule

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *yes* **Emergency Supply,** state

position and method of control of the emergency supply and how the generator is driven ☒

Navigation Lamps, are these separately wired *yes*, controlled by separate switch and separate fuses *yes*, are the fuses double pole *yes*

are the switches and fuses grouped in a position accessible only to the officers on watch *yes*

has each navigation lamp an automatic indicator as per Rule *yes* **Secondary Batteries,** are they constructed and fitted as per Rule *none*

are they ventilated as per Rule ☒

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *yes*

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *none*

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *Two lamps in each*

pump room protected by gaslight locked up boxes how are the cables led

outside pump room protected by gaslight tubes

where are the controlling switches situated *on navigation board*

are all fittings suitably ventilated *yes* are all switches and lampholders constructed wholly of non-ignitable, non-absorbent materials *yes*

Heating and Cooking Appliances, are they constructed and fitted as per Rule *none* are air heaters constructed and fitted as per Rule

Searchlight Lamps, No. of ☒ whether fixed or portable ☒ are their fittings as per Rule ☒

Motors, are their working parts readily accessible *yes* are the coils self-contained and readily removable for replacement *yes*

are the brushes, brush holders, terminals and lubricating arrangements as per Rule *yes* are the motors placed in well-ventilated compartments in which

inflammable gases cannot accumulate and clear of all inflammable material are they protected from mechanical injury and damage from

water, steam or oil *yes* are their axes of rotation fore and aft *yes* if situated near unprotected woodwork or other combustible

material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *none*

if not of this type, state distance of the combustible material horizontally or vertically above the motors ☒ and ☒

have machines of over 100 BHP been inspected by the Surveyors during manufacture and testing ☒ have certificates for all motors for

essential services been supplied and approved ☒

Control Gear and Resistances, are the generator field and motor speed

regulators, starters and controllers constructed and fitted as per Rule *yes* **Lightning Conductors,** where lightning conductors

are required, are these fitted as per Rule *yes* **Ships carrying Oil having a Flash Point less than 150° F.** Have the special requirements of

the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and

fittings *yes* are all fuses of the filled cartridge type *yes* are they of an approved type *yes*

If portable lamps for use in dangerous spaces are supplied, are they of a self-contained, battery-fed flameproof type approved for use in dangerous spaces *none*

Spare Gear, if the vessel is for open sea service have spares been supplied as per Rule *yes* are they suitably stored in dry situations *yes*

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN ...	1	16	110	146	390	Diesel engine	Kerosene	above 150°
AUXILIARY ...	1	16	110	146	390	Steam engine		
EMERGENCY ...								
ROTARY TRANSFORMER								

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	No. of Poles.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	Circuit.	Rule.			
MAIN GENERATOR ...	1		95 mm ²	19	2.53	146	150	16 ft	Rubber Lead covered & surrounded	
EQUALISER CONNECTIONS ...										
AUXILIARY GENERATOR ...	1		95 mm ²	19	2.53	146	150	10 "	"	"
EMERGENCY GENERATOR ...										
ROTARY TRANSFORMER MOTOR GENERATOR ...										
ENGINE ROOM ...	1		10 "	7	1.35	25	40	30 "	"	"
BOILER ROOM ...										
AUXILIARY SWITCHBOARDS ...										
ACCOMMODATION ...	1		16 mm ²	7	1.7	20	40	70 "	"	"
Sockets	1		10 "	7	1.35	20	40	30 "	"	"
Knives	1		16 "	7	1.7	36	40	170 "	"	"
Fuse ship	1		16 "	7	1.7	10	40	350 "	"	"
Navigation	1		10 "	7	1.35	35	40	190 "	"	"
Distribution Box	1		35 "	19	1.53	70	70	50 "	"	"
WIRELESS ...	1		16 "	7	1.7	37	40	180 "	"	"
SEARCHLIGHT ...	1		35 "	19	1.53	70	70	380 "	"	"
MASTHEAD LIGHT ...	1		1.5 "	1	1.38	0.5	10	120 "	"	"
SIDE LIGHTS ...	1		1.5 "	1	1.38	0.5	10	60 "	"	"
COMPASS LIGHTS ...	1		1.5 "	1	1.38	0.5	10	20 "	"	"
POOP LIGHTS ...	1		1.5 "	1	1.38	0.5	10	170 "	"	"
CARGO LIGHTS ...										
HEATERS ...										

MOTOR CONDUCTORS.

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP ...										
MAIN BILGE LINE PUMPS ...										
GENERAL SERVICE PUMP ...										
EMERGENCY BILGE PUMP ...										
SANITARY PUMP ...										
CIRC. SEA WATER PUMPS ...										
CIRC. FRESH WATER PUMPS ...										
AIR COMPRESSOR ...										
FRESH WATER PUMP ...										
ENGINE TURNING GEAR ...	1	1	50 mm ²	19	1.83	100	125	22 ft	Rubber Lead covered & surrounded	
ENGINE REVERSING GEAR ...										
LUBRICATING OIL PUMPS ...										
OIL FUEL TRANSFER PUMP ...										
WINDLASS ...										
WINCHES, FORWARD ...										
WINCHES, AFT ...										
STEERING GEAR—										
(a) MOTOR GENERATOR ...										
(b) MAIN MOTOR ...										
WORKSHOP MOTOR ...										
VENTILATING FANS ...	1	1	2.5 "	1	1.78	12	15	50 "	"	"
Bum pumps	1	1	2.5 "	1	1.78	8	15	10 "	"	"
Oil Separator	1	1	4 "	7	0.85	16	22	52 "	"	"
Drill	1	1	4 "	7	0.85	16	22	10 "	"	"
Lathe	1	1	2.5 "	1	1.78	12	15	8 "	"	"
Grinding	1	1	6 "	7	1.05	24	30	8 "	"	"

The Electrical Equipment is installed in accordance with the approved plans.

All Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

N.V. Groeneveld, Van der Poll & Co's

Electrotechnische Fabrik

Electrical Engineers.

Date 8/6 1938

COMPASSES.

Minimum distance between electric generators or motors and standard compass 75 M

Minimum distance between electric generators or motors and steering compass 73 M

The nearest cables to the compasses are as follows:—

A cable carrying 0.1 Ampères 2 M feet from standard compass 2 M feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes*

The maximum deviation due to electric currents was found to be *nil* degrees on course in the case of the standard compass, and *nil* degrees on course in the case of the steering compass.

Builder's Signature.

Date

Is this installation a duplicate of a previous case *yes* If so, state name of vessel *NY MARISA "Imp. 13993"*

General Remarks (State quality of workmanship, opinions as to class, &c.)

The electric installation has been made under special survey in accordance with approved plans. Secretary's letter Workmanship throughout good Tested installation under full working power found good

*Wid
L.F.
15/6/38*

Total Capacity of Generators 32 Kilowatts.

The amount of Fee ...

f 27.6

When applied for,

19

Travelling Expenses (if any) 0

When received.

16.6 19 38 f 18.6

B. J. J. J.
Surveyor to Lloyd's Register of Shipping.

FRI 17 JUN 1938

Committee's Minute

Assigned

See Ans. J.E. 15293



© 2020

Lloyd's Register
Foundation