

23 JUL 1946

Index No.

Rpt. C. 11 (Contd.)

Lloyd's Register of Shipping.

Ship's Name

KIRRIEMOOR

Official No. 164461.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

in 1935

Alterations or additions now found or made:

HATCHWAYS: On Shelter deck to tunnel escape trunk situated between Poop house wings.
 27" x 27", .40 channel coaming, 8" above wood deck over accommodation, with bolted steel plate cover
 Aft hatch to Prop store inside Poop house, 9" BA coaming with wood cover, 2 canvas covers & battening
 arrangements ✓

COMPANIONWAYS: Poop house on Shelter Deck, entrance to Prop tween deck accommodation, p+s
 5' x 2' 3", 19" sill, closed by hinged wood doors operated both sides. ✓

Aft end midship deckhouse, companionway constructed to shelter tween decks, steel casing, opening
 5' x 3' 3", 16" sill, closed by hinged steel doors, rubber jointed, with dog clips operated both sides. ✓

VENTS: Main holds & tween deck vents as now found: 4 @ 20" to N#1, 4+5 holds, 2 @ 20"
 to N#2 hold & 2 @ 24" derrick ports to N#2 hold suitably stayed 2 @ 15" to N#3 1, 2, 4+5 Tween decks,
 2 @ 12" to Deep tank. Coamings constructed in accordance with the rules provided with
 wood plugs & canvas covers ✓

1 @ 10" to tunnel escape on top of escape hatch, 19" coaming x 30 provided with wood plug &
 canvas cover. ✓

SCUPPERS: Overboard scuppers from Shelter tween decks disposed with and hauled off.
 4 scuppers, 2 each side abreast machinery casing, led to machinery space bays & provided
 with drop valves, now fitted in lieu. ✓

Two 5" overboard scuppers now fitted in tonnage well, provided with gun metal screw
 down non-return valves operated from above Shelter Deck ✓

Sanitary discharges from deckhouse accommodation fitted with ^{G.M.} storm valves at ship's side, discharging
 above freeboard deck ✓

FREING PORTS: Washports in after well welded up. ✓

MACHINERY CASING OPENINGS: In Shelter tween decks to machinery space port & starbd, openings
 each side 5'-8" x 23", 7" sill closed by hinged steel rubber jointed doors fitted with dog clips
 and operated from both sides ✓

The vessel is provided with a Poop deckhouse on shelter deck enclosing steering gear, stone
 hatch and part crew accommodation. Port & starbd forward extensions have now been
 built serving as Lamp room & Crews W.C. Steel construction! ✓

A copy of this report has been placed on board the ship.

MS.

C. Sheddan


27 June 1946.

Reed

JGD

15 JUL 1946

© 2020

Lloyd's Register
Foundation

004068-004075-0243