

Lloyd's Register of Shipping.

Ship's Name "MARGALAU"

Official No. 148748

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Crews accommodation transferred from forecastle tween decks to Poop space.

POOP BULKHEAD Opening closed by riveted plate.

SIDE SCUTTLES Fitted on ships side (p. & s.) 10" dia. with hinged deadlights.

VENTILATORS	3 @ 10" dia.	Coamings 32" x .38)	
	1 @ 9" "	" 32" x .38)	
	3 @ 6" "	" 32" x .30)	Fitted with wood plugs &
	4 Gooseneck	" 8" x 4")	canvas covers.
	1 "	6" x 4")	

Hatch on Poop Deck closed by welded plate on top of coaming. Fore and after and steel casings under.

Steel companionway fitted on top of hatchway, with solid wood.

Hatchway fitted on plate closing original hatchway, 2'-0" x 2'-0" x 9" B.A. coaming rest bars, wood covers, cleats, battens and two tarpaulins fitted.

George. Gallahue

GLASGOW, 15th June, 1946.



© 2020

Lloyd's Register
Foundation