

**COPY.**

(with Danzig First Entry Ref. No 400)  
S.S. 'SØRVANGEN.'

C o p y  
=====

Lloyd's Register of Shipping



Port of H a m b u r g

14th September 1928

This is to Certify that

Fr. S c h n e l l

the undersigned Surveyor to this Society did at the request of Messrs. Ottenser Eisenwerk A.G. of Altona-Ottensen test and examined on the 14 th September 1928 at their works, two sets "COLUMBUS" pattern Boats Davits (Type Lum G.K. 4) to be supplied to Messrs. International Shipbuilding Co.Ltd. of Danzig.

These davits have been constructed to the dimensions and scantlings as given on the approved plans and the steel and steel castings used in the construction have been tested as required by the Society's Rules and with satisfactory results.

Test on finished davits:

Each davit was tested by a static load equal to 5400 kgs corresponding to the total load 4500 Kgs. increased by 20%.

All parts were tested by hammering while the davits were under load, carefully examined afterwards and found in sound condition. No permanent deformation was found due to the test load applied.

For identification purposes the davits are stamped with the following consecutive numbers:

Lloyd's  
FS. No. 537/540  
14.9.28

Stempel



gez. Fr. Schnell  
Surveyor to Lloyd's Register

Lloyd's Register  
Foundation

004085-004092-0219