

## LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name S.T. "WAVE KNIGHT" Official No. 180875.

Port of Registry LONDON

This ship has been under survey at HEBBURN-ON-TYNE

on 19th December & Subsequently 1957/8 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:-

The Owners at this time have arranged for the following alterations to be effected.

4 New Longitudinal Cofferdams.

2 Longitudinal cofferdams between No.3 centre and No.3 wing cargo tanks p & s.

2 Longitudinal cofferdams between No.4 centre and No.4 wing cargo tanks p & s.

4 W.T. hatches to new cofferdams, 2 fitted in after well and 2 fitted within centre castle 23" x 18" coaming 8 x 4 x 60 angle with bolted .44 plate covers  $\frac{5}{4}$ " dia bolts 4" apart.

Additional Air Pipes:-

4-4" Dia. goosenecks 36" high (2p, 2s) in after well fitted with wire gauze and canvas covers.

Batterworth deck openings in way of Nos.3 & 4 wing cargo tanks (p & s) now blanked off.

J. A. Rigg.  
J.A. RIGG.

Noted  
all  
20.3.58

A copy of this Report has been placed on board.

