

Alexandra

268.08 x 39 x 19.50

(9) This vessel was built in 1931 and classed 100A1 in freeboard.

The Owners now request to be informed of the maximum draught that could be assigned with the present scantlings.

The vessel has a poop and bridge combined as a forecastle, the percentage of length covered by erections being 86.

The scantlings and arrangements have now been examined and it is found that while the longitudinal strength is equivalent to that required by the Rules for a full scantling vessel having 86% erections, the framing is only suitable for a vessel with 60% erections.

AM

10.5.38

WT.



© 2020

Lloyd's Register
Foundation

004116-004124-0157