

# REPORT ON ELECTRICAL EQUIPMENT.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office.....

Date of writing Report... 20. 11. 1948 When handed in at Local Office..... 19..... Port of... Liverpool

No. in Survey held at... Birkenhead Date, First Survey... Last Survey... 14/10/48  
Reg. Book. (Number of Visits.....)

78151 on the S.S. "TULIPFIELD" ex "NORLAND" Tons { Gross... 366  
Net... 165

Built at... Hamburg By whom built... Reichert's Schiffen. Yard No. ... When built... 1922

Owners... W. R. Metcalf Port belonging to... Liverpool

Electrical Installation fitted by... Grayson Rolfe & Co. Dock & Rep. Contract No. ... When fitted... 1948

Is vessel fitted for carrying Petroleum in bulk... No Is vessel equipped with D.F. No E.S.D. No Gy.C. No Sub.Sig. No

Have plans been submitted and approved... Yes System of Distribution... Two wire Voltage of supply for Lighting... 110

Heating... Power... Direct or Alternating Current, Lighting... DC Power... If Alternating Current state periodicity... Prime Movers,

has the governing been tested and found as per Rule when full load is suddenly thrown on and off... Yes Are turbine emergency governors fitted with a

trip switch as per Rule... Generators, are they compound wound... Yes, are they level compounded under working conditions... Yes,

if not compound wound state distance between generators... and from switchboard... Where more than one generator is fitted are they

arranged to run in parallel... No, are shunt field regulators provided... Yes Is the compound winding connected to the negative or positive pole

negative Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing... Have certificates of

test for machines under 100 kw. been supplied... No and the results found as per rule... Are the lubricating arrangements and the construction

of the generators as per rule... Yes Position of Generators... In engine room.

is the ventilation in way of generators satisfactory... Yes are they clear of inflammable material... Yes, if situated

near unprotected combustible material state distance from same horizontally... and vertically... are the generators protected from mechanical

injury and damage from water, steam and oil... Yes, are the bedplates and frames earthed... Yes and the prime movers and generators in metallic

contact... Yes Switchboards, where are main switchboards placed... In engine room adjacent to generators.

are they in accessible positions, free from inflammable gases and acid fumes... Yes, are they protected from mechanical injury and damage from water, steam

and oil... Yes, if situated near unprotected combustible material state distance from same horizontally... and vertically... what insulation

material is used for the panels... Siemens., if of synthetic insulating material is it an Approved Type... Yes, if of

semi-insulating material (slate or marble) are all conducting parts insulated therefrom as per Rule... Is the frame effectually earthed... Yes

Is the construction as per Rule... Yes, including accessibility of parts... Yes, absence of fuses on the back of the board... Yes, individual fuses

to pilot and earth lamps, voltmeters, etc.,... Yes locking of screws and nuts... Yes, labelling of apparatus and fuses... Yes, fuses on the "dead"

side of switches... Yes Description of Main Switchgear for each generator and arrangement of equaliser switches... Double pole switch

and double pole fuses.

and for each outgoing circuit... Double pole switch and double pole fuses.

Are compartments containing switchboards composed of fire-resisting material or lined as per Rule... Instruments on main switchboard... 2

ammeters... 2 voltmeters... synchronising devices. For compound machines in parallel is the ammeter connected on the pole opposite to the

equaliser connection... Earth Testing, state means provided... Local indicating lamps.

Switches, Circuit Breakers and Fuses, are they as per Rule... Yes, are the fuses an approved type... Yes, are all fuses labelled as

per Rule... Yes If circuit breakers are provided for the generators, at what overload current did they open when tested... are the reversed current

protection devices connected on the pole opposite to the equaliser connection... have they been tested under working conditions, and at what current

did they operate... Joint Boxes, Section Boards and Distribution Boards, is the construction and position as per Rule... Yes

Cables, are they insulated and protected as per the appropriate Tables of the Rules... Yes, if otherwise than as per Rule are they of an approved type...

state maximum fall of pressure between bus bars and any point under maximum load... 2.7 Volts, are the ends of all cables having a sectional area of 0.04

square inch and above provided with soldering sockets... Yes Are paper insulated and varnished cambric insulated cables sealed at the ends...



PARTICULARS OF GENERATING PLANT

Lloyd's Register  
Foundation



The Electrical Equipment is installed in accordance with the approved plans and the requirements of the Rules.  
All Insulated Conductors are guaranteed to have been tested at the maker's works as specified in the Rules.  
The foregoing is a correct description.

OR AND ON BEHALF OF  
GRAYSON, ROLLO & CLOVER DOCKS LTD,

*A. Stewart*

Electrical Engineers.

Date *3<sup>rd</sup> December 1948*

#### COMPASSES.

Minimum distance between electric generators or motors and standard compass..... *60 ft*

Minimum distance between electric generators or motors and steering compass..... *50 ft*

The nearest cables to the compasses are as follows:—

A cable carrying *3* Ampères *8* feet from standard compass *6* feet from steering compass.

A cable carrying *11.8* Ampères *15* feet from standard compass *12* feet from steering compass.

A cable carrying *20* Ampères *4* feet from standard compass *4* feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power..... *Yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted..... *Yes*

The maximum deviation due to electric currents was found to be..... *Compass adjusted before vessel put in service - deviation not available* degrees on..... course in the case of the

standard compass, and..... degrees on..... course in the case of the steering compass.

Builder's Signature. Date.....

Is this installation a duplicate of a previous case..... *No* If so, state name of vessel.....

Plans. Are approved plans forwarded herewith..... *Yes* If not, state date of approval.....

Certificates. Are certificates of test for motors engaged on essential services and generators forwarded herewith..... *No - Existing original generators.*

General Remarks (State quality of workmanship, whether insulation tests, etc., have been made, opinions as to class, etc.)..... *The electrical*

*equipment of this vessel has been installed under special survey in accordance with the approved plans & Rules for Electrical Equipment. The original installation, with exception of the generators, was stripped out. The original generators were overhauled and retained. On completion the equipment was tested under full working conditions & found satisfactory. The material & workmanship are good.*

*In my opinion this electrical equipment is eligible to be accepted for classification.*

*See endorsement of 8/12/49*

Total Capacity of Generators..... *15* Kilowatts.

The amount of Fee ... £ *10* : *0* : *0* When applied for, *24 DEC 1948*

Travelling Expenses (if any) £ : : When received, .....

*H. Haffner*  
Surveyor to Lloyd's Register of Shipping.

FIL 25 MAR '49

Committee's Minute..... *LIVERPOOL 29 DEC 1948*

Assigned..... *See Minute re Liverpool Mch. Rpts. J.*



© 2020

Lloyd's Register  
Foundation