

Lloyd's Register of Shipping.

Ship's Name "NASSAU" ex EUROPA

Signal letters

~~Official No.~~

HOVC

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in June 1950 at Genoa.

A) Particulars of additional ventilators fitted on shade (superstructure) deck

	dia.	thickness	height of coamings	closing appliances
- 2 ventilators between No 2 & No 3 hatchways:	24"	.40	44" efficiently supported by brackets	✓ wood plugs with canvas covers
- 1 ventilator between No 2 & No 3 hatchways:	16"	.40	36"	✓ mushroom with canvas cover
- 2 ventilators aside deckhouse aft (p.d.c.) connected to fans.	16" x 19"	.40	30"	✓ W.T. dampers

B) Gangway etc.

A shell door now fitted on each side, between freeboard and superstructure decks; opening on shipside 6'-6" height x 4'-2" width, closed by hinged watertight doors of strength as the shell, secured by twelve screw fastenings.

C) Particulars of protection to openings, etc.

On promenade deck (superimposed on superstructure deck)

- Height of coaming of No 4 hatchway reduced to 18".
- The opening of skylight abaft No 6 hatchway now permanently closed by a welded plate supported by longitudinal webs bracketed to the coaming.

Montan

Genoa, 1st December 1951

G.H.W.

6- DEC 1951



© 2021

Lloyd's Register
Foundation