

PORT on the

mean Makarov. Lb. No. 29.

$$\text{med.:- } 390.0 \times 58.3' \times \left. \begin{array}{l} 28.0' \\ 36.0' \end{array} \right\}$$

1) As a full scantling ship with actual erection but with 50% excess sheer, and a moulded depth of 36'-0" to the upper deck, the summer moulded draught = 29'-1/2

2) The equivalent moulded depth of a full scantling ship with actual erection and 50% excess sheer to give the desired draught of 26'-6" (moulded) = 32'-4"

Copy to W. bearing.



© 2021

Lloyd's Register
Foundation

004184-004193-0160

270.75 = 1.71 ✓

Winter Freeboard from deck line