

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "ALTIS" Official No. 1147

Port of Registry MONROVIA.

This ship has been under survey at HULL.

on 10th May, 1958 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:—

Vessel converted from "Open" to "Closed" shelter deck.

Tonnage hatch permanently closed watertight by means of a .40" thick plate welded to the existing bulh angle coaming. Plate stiffened by means of a 6" x 3" inverted ordinary angle welded toe on to underside. Stiffener, fitted athwartships, is bracketed at ends to inside of side coamings.

Access to the tonnage well provided through a 24" x 24" hatch, coaming 24" above top of new closing plate 0.40" thick.

Opening closed by a wood cover 3" thick and secured by cleats, tarpaulins, battens and wedges.

Provision made for the fitting of a lifeline on Upper deck.

Lifelines of wire rope with bottle screws.

J.H. Subeiffe
SURVEYOR TO LLOYD'S REGISTER
OF SHIPPING, H U L L.

Nulen
AR
15.5.58

A copy of this Report has been placed on board.



© 2020

Lloyd's Register
Foundation

004194-004199-0412