

COPY

Reports.
for Ship Dept -

AIR MAIL

LLOYD'S REGISTER OF SHIPPING

71, Fenchurch Street, London, E.C.3

Telegrams: Committee, Fen, London

23rd January, 1958.

Telephone: ROYal 9166

Dear Sirs,

"SHUN FUNG" to be renamed "MORO"

Fbd.

I acknowledge receipt of your letter of the 15th instant regarding the above ship which is to be transferred to the Panamanian flag and in reply would inform you that the ship is not suitable for the new service proposed without considerable reinforcement to the floors and frames.

The following items will also require to be dealt with:-

1. The coamings of No. 3 shelter deck hatchway forward of the 4' tonnage hatch being increased in height to 18".
2. Locking bars or special wire lashings independently set up with warwick screws being provided for No. 1 hatch on the shelter deck
3. Overboard discharges from spaces in the 'tween decks being fitted with screw down automatic non-return valves controlled from positions on the freeboard deck always accessible under service conditions.
4. The door on the forward companionway to be of hardwood 2" thick.

Yours faithfully,

Copy to Djakarta

pro Secretary.

The Surveyors,
HONG KONG

CFA.

W. A. 281



© 2021

Lloyd's Register
Foundation