

## LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name S.S. "SHUN FUNG" ex "Tung Song" Official No. 132317

Port of Registry Hong Kong.

This ship has been under survey at Hong Kong,

on 20th March, 1956 and the following alterations to the conditions of

assignment of loadlines have now been effected/found:—

Gangway, Cargo & Coaling Ports in Ship's side.

Cargo doors removed and openings permanently closed.

Side Vent doors, excluding two lp. ls. abreast E.R., removed and openings permanently closed.

Companionways on Superstructure Deck.

Companion Ladder aft removed and deck opening permanently closed.

Companionway fitted in after deck house. Casing steel, 6/20, stiffeners 2½" x 2½" x 5/16" spaced 20", Door opening 4'-10" x 24" strongly framed, Sill 18",

Door steel, hinged, watertight and capable of being operated from both sides.


Air Pipes

All air pipes from deep, double bottom and settling tanks previously led to main deck now extended to shade deck. Opening 3'-0" above deck and fitted with gauze wire and canvas covers.

Scuppers

Overboard scuppers from main deck removed and shell and deck openings permanently closed.

Four 3" dia scupper pipes, 2p. 2s., led from main deck to machinery space and fitted with self closing cocks.

  
James A. Anderson.

Surveyor to Lloyd's Register,

HONG KONG,


20th March, 1956.

Noted

J.H.

2. 5. 56.

A copy of this Report has been placed on board.



© 2021

Lloyd's Register  
Foundation

004213-004221-0234