

Lloyd's Register of Shipping.

31 OCT 1946

Ship's Name

" WANDLE "

Official No. 163297

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

SKYLIGHTS: 2 skylights to after accommodation fitted against casing on Raised Quarter Deck, starboard side. Coaming of steel, 16" high outboard, 19" at casing, above wood decking opening 24"x18" closed by hinged wood frame with glass protected by steel bars. Chocks, battens, wedges and 2 tarpaulins per skylight provided for battering down.

ASH SHOOT. Opening in casing (ps) on Raised Quarter deck 18"x18", coaming 18" high, closed by hinged steel door operated from both sides.

FOCLE BULKHEAD. Opening p+s closed by hinged steel doors operated from both sides.

A copy of this report has been placed on board.

C. D. Snedden . 18/10/46.

W. Steel
J. D. W.

31 OCT 1946

ML-12