

G.R. 130.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) G.B.M.F.

Official Number.	Name of Ship.		No., Date, and Port of Registry.	
180361	EMPIRE JUMNA		8 in 1944 Grangemouth	
No., Date, and Port of previous Registry (if any).				
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steamship Single Screw	Grangemouth	1944	The Grangemouth Dockyard Co. Ltd., Grangemouth.
Number of Decks One	Length from fore part of stem, to the aft side of the head of the stern post 290	Feet.	Tenths.	
Number of Masts Two	Main breadth to outside of planking 44			
Rigged Not	Depth in hold from tonnage deck to ceiling amidships ... 19			
Stem Straight	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards -			
Stern Cruiser	Depth from top of deck at side amidships to bottom of keel... 19			
Build Clencher	Round of beam -			
Framework and description of Steel vessel Oil Carrier	Length of engine room, if any 54			
Number of Bulkheads Eleven O.T.				
	One W.T.			

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines	Description of Engines	Whether British or Foreign Made	When made	Name and address of makers	Reciprocating Engines		Rotary Engines	N.H.P. B.H.P. I.H.P. Estimated Speed of Ship
					No. and Diameter of Cylinders in each set	Length of Stroke		
One	Reciprocating, Steam, Direct Acting, Vertical, Inverted Cylinder, Triple Expansion	Engines British	Engines 1944	Engines and	Three 18"	39"		242 1250
No. of Shafts	Particulars of Boilers Cylindrical Description... Multitubular Number One..... Iron or Steel. Steel..... Loaded Pressure .220 lbs. per sq. in.	Boilers British	Boilers 1944	Boilers David Rowan & Co. Ltd., Glasgow.	31" 52"			10 1/2 Knots

Number of water ballast tanks, and their capacity in tons:— Three — 157 tons.

(P.T.O.)

004263-804274-0120

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	1752.22	On account of space required for propelling power	758.56
Space or spaces between Decks	-	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.	218.58
Turret or Trunk	238.73	These spaces are the following, viz. :—	
Forecastle	7.49	Poop, Bridge and Deck House	
Bridge space	131.93	(Number of Seamen or Apprentices for whom accommodation is certified.....33.....).	
Poop or Break	139.00	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—	
Side Houses in Forecastle	11.61	Cubic Meters.	
Deck Houses	35.76	Master's Accommodation 11.79	
Chart House	-	Chart Space 5.81	
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	53.75	W/T Space 9.01	
Excess of Hatchways	-	Lobby .50	
Gross Tonnage	2370.49	Boatswains Store 11.33	112.06
Deductions, as per contra	1089.20	Ballast Pump Spaces 25.53	
Register Tonnage	1281.29	Total	1089.20
		Water Ballast Spaces 48.09	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is.....256.96.....tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is.....87.97.....tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle L = 26.0 ft. = 28.39 tons.

Name of Master John Michael Banks

Certificate of { Service No. Competency No. 47967

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

His Majesty represented by the Minister of War Transport, London.
(64) Sixty four Shares.

Mgr: James Huntley of Hadley Shipping Company Limited, 53, Leadenhall Street, London, E.C.3.

Dated 28th December 1944

Wt. 250. Gp. 39. 1,000 6/44. H.T. Ltd. W362.

Where Fitted.

Length.

Water Capacity.

Where Fitted.

Length.

Water Capacity.