

REPORT ON BOILERS.

SEA. No. 3454

19 AUG 1942

Received at London Office

Date of writing Report 19 When handed in at Local Office 19 Port of SEATTLE, WASHINGTON

No. in Survey held at Seattle, Washington Date, First Survey October 1st Last Survey December 30 1941

opening in Reg. Book. on the Todd-California Shipbuilding Corp., Yard No. 20. "Ocean Volga" (Number of Visits 22)

Master Built at Richmond, Cal. By whom built Todd-Calif. Shipbldg. Corp. When built 1941

Engines made at Hamilton, Ohio By whom made General Machinery Corporation When made 1942

Boilers made at Seattle, Wash. By whom made Puget Sound Machinery Depot When made 1941

Registered Horse Power 505 Owners British Government Port belonging to London

MULTITUBULAR BOILERS—MAIN, AUXILIARY OR DONKEY—Manufacturers of Steel Lukens, Carnegie-Illinois, S. Cos.

(Letter for record S) Total Heating Surface of Boilers 7140 sq. ft. Is forced draft fitted No. and Description of Boilers One - Scotch, Single Ended Working Pressure 220 lbs Tested by hydraulic pressure to 380 lbs Date of test Dec. 22

No. of Certificate No. 8 Can each boiler be worked separately Area of fire grate in each boiler 52 sq. ft. No. and Description of safety valves to each boiler Area of each valve Pressure to which they are adjusted Are they fitted with easing gear In case of donkey boilers, state whether steam from main boilers can enter the donkey boiler Smallest distance between boilers or uptakes and bunkers or woodwork Max. dia. of boilers 14' 9" Length 11' 9"

Material of shell plates Steel Thickness 1-13/32" Range of tensile strength (75,000) Are the shell plates welded or flanged No

Descrip. of riveting: cir. seams D.R. long. seams T.R.D.B.S. Diameter of rivet holes in long. seams 1 1/2" Pitch of rivets 5" & 10"

or width of butt straps 22-1/8" Per centages of strength of longitudinal joint rivets 93.4 Working pressure of shell by rules 221.2 lbs Size of manhole in head 3- 12" x 16" Size of compensating ring Flanged No. and Description of Furnaces in each boiler 3-Corrugated Material Steel Outside diameter 44-9/16" Length of plain part top 7-13/16" Thickness of plates crown 21/32" Description of longitudinal joint Forge weld No. of strengthening rings - Working pressure of furnace by the rules 230 lbs Combustion chamber plates: Material Steel Thickness: Sides 25/32" Back 25/32" Top 25/32" Bottom 25/32" Pitch of stays to ditto: Sides 10-3/16" Back 9" x 9"

Top (x 11" If stays are fitted with nuts or riveted heads (Nuts inside) Rivets out Working pressure by rules 224# Material of stays Steel Area at smallest part (2.06" (81.0 sq. ins. (224 lbs) Dblr. 1-1/32"

Pitch of stays 21" How are stays secured D. Nuts Working pressure by rules 221 Material of stays Steel Area at smallest part 9.6 sq. ins.

Area supported by each stay 441 sq. ins. Working pressure by rules 245# Material of Front plates at bottom Steel Thickness 1-1/32" Material of Lower back plate Steel Thickness 1-1/32" Greatest pitch of stays 9" x 9" Working pressure of plate by rules 232 Diameter of tubes 3"

Pitch of tubes (4-1/4" Material of tube plate Steel Thickness: Front 1-1/32" Back 13/16" Mean pitch of stays 9-7/16" Pitch across wide water spaces 14 1/2" Working pressures by rules 232 lbs Girders to Chamber tops: Material Steel Depth and thickness of girder at centre (x 7/8" Length as per rule 34" Distance apart 11" Number and pitch of Stays in each 3 - 7-5/8"

Working pressure by rules 229 Steam dome: description of joint to shell - % of strength of joint -

Diameter - Thickness of shell plates - Material - Description of longitudinal joint - Diam. of rivet holes -

Pitch of rivets - Working pressure of shell by rules - Crown plates - Thickness - How stayed -

SUPERHEATER. Type - Date of Approval of Plan - Tested by Hydraulic Pressure to -

Date of Test - Is a Safety Valve fitted to each Section of the Superheater which can be shut off from the Boiler -

Diameter of Safety Valve - Pressure to which each is adjusted - Is Easing Gear fitted -

VERTICAL DONKEY BOILER— No. - Description - Manufacturers of steel -

Made at - By whom made - When made - Where fixed - Working pressure -

Tested by hydraulic pressure to - Date of test - No. of Certificate - Fire grate area - Description of safety valves -

No. of safety valves - Area of each - Pressure to which they are adjusted - If fitted with easing gear - If steam from main boilers can enter the donkey boiler -

Dia. of donkey boiler - Length - Material of shell plates - Thickness - Range of tensile strength -

Descrip. of riveting long. seams - Dia. of rivet holes - Whether punched or drilled - Pitch of rivets -

Per centage of strength of joint Rivets - Working pressure of shell by rules - Thickness of shell crown plates -

Plates - No. of Stays to do. - Dia. of stays - Diameter of furnace Top - Bottom - Length of furnace -

Thickness of furnace plates - Description of joint - Working pressure of furnace by rules - Thickness of furnace crown plates -

Radius of do. - Stayed by - Diameter of uptake - Thickness of uptake plates -

Thickness of water tubes -

The foregoing is a correct description, Puget Sound Machinery Depot Manufacturer.

Oct: 1, 18, 28, 31. Nov: 5, 9, 13, 17, 24, 26, 28
Dec: 1, 2, 3, 7, 11, 12, 18, 22, 27, 29, 30.

During progress of work in shops -
During erection on board vessel -
Total No. of visits 22

Is the approved plan of main boiler forwarded herewith -
" " " donkey " " "

© 2020 Lloyd's Register Foundation

004275-004284-0066

GENERAL REMARKS (State quality of workmanship, opinions as to class, &c.)

The Scotch marine single ended boiler herein mentioned has been built under special survey and in accordance with the Rules and approved plan. The materials tested as required by the Rules and together with workmanship, found good throughout. This boiler has now been forwarded to Todd-California Shipbuilding Corp., Richmond, California, stated to be fitted on board their Hull No. When this has been done in accordance with the Rules, to the Surveyor's satisfaction the boiler will be eligible in my opinion to receive the Notation 220 lbs in the Register Book.

Date of writing
No. in Reg. Book.
Master
Engines ma
Boilers ma
Registered
MULTI
Letter for
Boilers On
No. of Cen
afety val
Are they fi
Smallest a
Material
Descrip. o
rules 221
boiler 3
Descriptio
plates: A
(7-5
Top (x 1
smallest p
Pitch of
Area sup
Lower ba
Pitch of
water spo
rder at
Working
diameter
Pitch of r
PER
ate of T
diameter c
ERT
ade at
sted by
n. of sa
ter the
length
p of p
dus of
ickness
tes
ickness

Certificates (if required) to be sent to
(The Surveyors are requested not to write on or below the space for Committee's Minute.)

The amount of Entry Fee .. £		When applied for.
Special	\$108.6119.....
Donkey Boiler Fee £	:	When received,
Travelling Expenses (if any) £	\$4.0019.....

WES

W. Smith
Engineer Surveyor to Lloyd's Register of Shipping

Committee's Minute NEW YORK JUL 29 1942
Assigned See Richmond Rpt. NO. 20