

37609

30 SEP 1954

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name *"Wave Emperor"*

Official No. 180034.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in *October 1953.*

1 Steel W.I. hatch fitted on Upper Deck for access to new emergency fire pump room situated on Star. side immediately fwd of fwd cofferdam, and on 2nd dk. Hatch coaming 14" high x 50", opening 2'0" x 2'0", with .50" thick hinged W.I. steel lid, fastened by 4 clips.

Supply to fire pump taken by branch line from fwd ballast pump sea suction, with S.D.N.R.V. fitted, controlled from Upper Deck, with open/closed indicator at U. Deck.

J. B. Somerville.
1.9.54.

[Signature]
9 OCT 1954



© 2020

Lloyd's Register
Foundation