

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "Wave Conqueror" Official No. 169132

Port of Registry London.

This ship has been under survey at Wallsend - on - Tyne.

on 28th September 1954. and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~—

An emergency fire pump has been fitted in a separate compartment built into the after port corner of the fore hold with an access hatch and ventilator fitted on the upper deck

Access Hatch: Steel coaming 33" above deck x .50" thick
Hatch Dimensions ~ 1'-8" x 2'-2"
Opening in Deck ✓ 18" x 24" Oval.
fitted with a hinged steel W.I cover .50" thick and secured by 8 toggles ✓

Ventilator on Foreboard Deck: 6" diameter cowl vent, coaming ✓
36" high above deck x .34 thick and provided with wood plug and canvas cover.

Le Buchanan

15-10-54.

Newcastle-on-Tyne

[Signature]

23 OCT 1954

20

A copy of this Report has been placed on board.

