



Lloyd's Register of Shipping,

LLOYD'S REGISTER,
LONDON.

Malmö, 18th November 1919.

REC'D 24 NOV 1919

ANSP

The Secretary,

LONDON.

Dear Sir,

I beg to acknowledge the receipt of your telegram respecting A.B. Oresundsvarvet's Yard No. 3, steamer "COPENHAGEN", viz.:

"Steamer Copenhagen warxowaukt wavyrwazep wazyvwebmo wefsuwemah"

"Steamer Copenhagen the freeboard assigned is one foot 8 inches from top of statutory deck line to centre of disc. The statutory deck line is 1 1/2 inches above the steel deck at side. The other lines should be marked, as follows: F.W. 5 inches above centre of disc, I.S. 4 inches above centre of disc, W. 4 inches below centre of disc, W.N.A. 6 inches below centre of disc, subject to efficient temporary covers being fitted over tonnage opening in accordance with the freeboard rules for shelter deck vessels".

The Builders have been informed accordingly.

I am, Dear Sir,

Yours faithfully,



© 2021

Lloyd's Register
Foundation


004292-004299-0318

midships, n
not taken
with side.

Referred to the Chief Ship Surveyor.



NOV 24 1899



© 2021

Lloyd's Register
Foundation