

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C. 3.

2 ENCLOSURES.

17th November, 1919.

Dear Sir,

I have to confirm the telegrams which have passed between us as follows, namely,

Received =

"STEAMER COPENHAGEN

"YCDUJ = Report was forwarded

"ZEIRP = 7th November.

Sent =

"STEAMER COPENHAGEN

"WARXOWAUKT = The freeboard assigned is 1'-8" from top of statutory deck line to centre of disc.

"WAVYRWAZEP = The statutory deck line is 1½" above the iron (steel) deck at side. The other lines should be marked as follow:- Fresh water 5" above centre of disc.

"WAZYVWEBMO = Indian summer 4" above centre of disc; Winter 4" below centre of disc.

"WEFSUWEMAH = Winter North Atlantic 6" below centre of disc. Subject to efficient temporary covers being fitted over tonnage opening in accordance with the Freeboard rules for shelter deck steamers.

The printed letters of assignment are enclosed herewith.

I am, Dear Sir,

Yours faithfully,

G. W. Jorgensen, Esq.,
MALMO.

Secretary.

004292-004299-0321