

Translation of Cable sent to Malmo Surveyor on
17th November, 1919.

STEAMER COPENHAGEN = Vessel's name.

WARXOWAUKT = The freeboard assigned is 1'-8"
from top of statutory deck line to
centre of disc.

WAVYRWAZEP = The statutory deck line is 1 $\frac{3}{4}$ " above
the iron (steel) deck at side. The
other lines should be marked as
follows:- Fresh water 5" above centre
of disc.

WAZYVWEBMO = Indian summer 4" above centre of disc;
Winter 4" below centre of disc.

WEFSUWEMAH = Winter North Atlantic 6" below centre
of disc. Subject to efficient
temporary covers being fitted over
tonnage opening in accordance with
the Freeboard rules for shelter deck
steamers.



© 2021

Lloyd's Register
Foundation

004292-004299-0322