

6-JUL 1956

Index No.
(For London Office use)

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "WAVE GOVERNOR"Official No. 180489Port of Registry LONDONThis ship has been under survey at EDGEMUE DOCKYARD, GLASGOWduring MAY/JUNE 1956~~AND~~and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:-1.) ACCESS HATCH TO FIRE PUMP COMPARTMENT (S.S.)

Existing access hatch to Emergency Fire Pump space (forward hold S.S.) now blanked off at upper deck level, with welded steel plate, and new opening cut in exposed upper deck (2'3" x 2'3") about 2. frame spaces aft of Paint locker and bulkhead. Compensation provided in way of deck opening, framing 2'9" x 5'0" with steel watertight hinged lid, 3/8" thick, secured by hinges & toggles. ✓

On completion of work, upper deck was tested in way of blanked off previous opening, also now fitted craming and lid was tested and found satisfactory. ✓

2.) BUTTERWORTH OPENINGS (ADDITIONAL)

2. additional Butterworth openings (1. p s i. s.) now fitted at upper deck level in way of No. 4. Cargo Wing tank (p s s.) Adequate compensation provided in way of deck openings. ✓



1000
13-7-56

A copy of this Report has been placed on board.



© 2020

Lloyd's Register
Foundation

004300-004307-0036