

POSTPONED SURVEYS

S.S. "SUD" No. 78953 in R.B.

Tonnage Owners

Port of Registry

53

Special Survey due 11.48 - part held.

Boiler Survey due 7.54.

Recommended main boilers to be retubed, both boiler combustion chamber tube, back and wrapper plates to be part renewed with screw stays in way. Several screw and longitudinal stays to be renewed in both boilers. Thrust shaft collars to be skimmed and bearing collars remetalled, lower half ~~held~~ crankshaft bearings to be remetalled and the shafting re-aligned.

Screwshaft Survey due 5.55.

Special Survey was commenced in April/August, 1954, at Buenos Aires. The vessel was laid up pending a decision as to her future, reported that due to the necessity for major repairs to the vessel, the vessel might be broken up.

In reply to enquiry the Buenos Aires Surveyors now state the vessel is still laid up but the Owners are endeavouring to obtain the permit to import new boilers. If and when the new boilers are obtained all outstanding surveys will be dealt with.

Recommendations

TUESDAY 26 JUL 1955

Amtd.

*Robert
17*

© 2020

Record 'Laid up' Surveys

overline

Lloyd's Register
Foundation

004308-004315-0151

(29)
if chargeable)

70.00

Received by me,

N. Vaylor

